

Customer Pre-Template Checklist

The worksite must be prepared as described below prior to the templating appointment:

_____ All cabinets/vanities to receive stone tops must be:

- Structurally sound
- Fully installed
- Properly secured to the wall and/or floor; and
- Level

_____ The following items need to be available on site, if applicable to the project. It may be necessary for The Stone Studio to take these items back to the shop to ensure proper fit into the final stone product.

- Sinks (unless provided by The Stone Studio)
- Faucets
- Cooktops
- Pop-up style cooktop vents
- Soap dispenser
- Sprayer
- Water Dispenser
- Any other item that will require a hole to be cut into the stone

_____ The following items must be completed, if applicable to the project:

- Corbels installed (unless provided by The Stone Studio)
- Apron sink placed in sink cabinet, but not attached

_____ If an item such as an appliance garage, tambour doors, or other cabinet is to sit directly on top of countertop, this item CANNOT be installed until AFTER the new countertop is fully installed.

_____ The Customer or the Customer's authorized representative must be available throughout the duration of the Templating Appointment and be prepared to make any final design or placement decisions required.

_____ Signed contract and deposit must be received before template appointment.

Customer Pre-Installation Checklist

The worksite must be prepared as described below prior to the installation appointment:

_____ All items on the templating checklist must be completed.

_____ Existing countertops must be removed, if applicable. (unless this service is to be provided by The Stone Studio)

_____ There must be a roadway or driveway providing access for The Stone Studio to park its vehicle within a reasonable distance of the worksite to unload the stone.

_____ There must be an unobstructed path from an exterior door to the worksite so The Stone Studio can bring the stone product in for installation.

_____ No other activities may be taking place in the immediate vicinity of the worksite for the duration of the installation appointment (ie, no contractors working on painting, lighting, flooring, etc. in the same room at the same time)